

Designation: 3W-31-72

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q18-10

Page/Grid: 953/C-1

City / Location: Unin., Orange Co.

Line #/SSN: 370/0250

Established By: OCS 1972

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk

NO PHOTO

NAVD88 (ft)	NGVD29 (ft)	Year Leveled
379.002	376.665	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 33 03.8	117 35 20.7

Description:

DESCRIBED BY OCS 1972 5.3 MILES NORTHEAST ALONG ORTEGA HIGHWAY (STATE HIGHWAY 74) FROM ITS INTERSECTION WITH THE SAN DIEGO FREEWAY (INTERSTATE 5) TO A PAVED ROAD ON THE LEFT, TURN LEFT AND PROCEED 0.4 MILE NORTH ON THE PAVED ROAD TO A FORK IN THE ROAD, TAKE THE RIGHT FORK AND PROCEED 0.2 MILE NORTH ON THE PAVED ROAD TO A DIRT ROAD ON THE LEFT, TURN LEFT AND PROCEED 0.8 MILE WESTERLY ON THE DIRT ROAD AS IT FOLLOWS ALONG THE BASE OF THE HILL TO A DIRT ROAD ON THE RIGHT WHICH LEADS TO CANADA GOBERNADORA, TURN RIGHT AND PROCEED 2.25 MILES NORTH ON THE DIRT ROAD, 12 FT. EAST OF THE DIRT ROAD, 4 FT. WEST OF A BARBED WIRE FENCE, 44 FT. NORTH OF A 6 INCH BY 8 INCH WOOD FENCE POST IN THE BARBED WIRE FENCE, 94.5 FT. SOUTHEAST OF A 4 INCH WATER RISER, 2 FT. WESTERLY OF A STEEL WITNESS POST, SET IN THE TOP OF A CONCRETE POST, 0.5 FT. HIGHER THAN THE ROAD.

