

## Designation: 3W-58-79

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q14-09

Page/Grid: 862/J-4

City / Location: Trabuco Canyon

Line #/SSN: 370/0030

Established By: OCS 1979

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
1351.888	1349.525	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 40 59.99	117 36 12.58

### Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3W-58-79", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED IN THE NORTHERLY CORNER OF THE INTERSECTION OF LIVE OAK CANYON ROAD AND HAMILTON TRAIL, 1.2 MILES EASTERLY ALONG LIVE OAK CANYON ROAD FROM THE CENTERLINE OF SANTIAGO CANYON ROAD, 16 FT. NORTHWESTERLY OF THE CENTERLINE OF HAMILTON TRAIL AND 46 FT. NORTHERLY OF THE CENTERLINE OF LIVE OAK CANYON ROAD.

