

Designation: 404-22-86

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q07-02

Page/Grid: 739/J-7

City / Location: Placentia

Line #/SSN: 404/0210

Established By: OCS 1986

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
241.756	239.350	2006
241.796	239.398	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 52 02.10	117 50 13.24

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "404-22-86", SET IN THE NORTHERLY CORNER OF A CONCRETE HEADWALL. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF THE ATWOOD CHANNEL AND JEFFERSON STREET, 19 FT. EASTERLY OF THE CENTERLINE OF JEFFERSON AND 449 FT. SOUTHERLY OF THE CENTERLINE OF ORANGETHORPE AVENUE. MONUMENT IS SET LEVEL WITH THE TOP OF THE WALL.

