

Designation: CC-12

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q05-07

Page/Grid: 767/A-6

City / Location: Cypress

Line #/SSN: 401/0150

Established By: USCE

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
44.593	42.172	2005
44.689	42.212	1994

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 49 53.42	118 03 46.20

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" US ARMY CORPS OF ENGINEERS BRONZE DISK STAMPED "CC-12-58", SET IN THE SOUTHWEST CORNER OF A CONCRETE BRIDGE ABUTMENT. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF LINCOLN AVENUE AND THE COYOTE CREEK CROSSING, 40 FT. SOUTHERLY OF THE CENTERLINE OF LINCOLN AVENUE AND 6 FT. EASTERLY OF THE SOUTHWESTERLY CORNER OF THE BRIDGE. MONUMENT IS SET 1.0 FT. BELOW THE ROAD.

