

Designation: CC-13

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q05-07

Page/Grid: 767/A-6

City / Location: Cypress

Line #/SSN: 401/0160

Established By: USCE

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
44.723	42.301	2005
44.826	42.349	1994

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 49 54.21	118 03 46.06

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" US ARMY CORPS OF ENGINEERS BRONZED DISK STAMPED "CC-13-1958", SET IN THE NORTHWEST CORNER OF A CONCRETE BRIDGE ABUTMENT. MONUMENT IS LOCATED IN THE NORTHWESTERLY CORNER OF THE INTERSECTION OF LINCOLN AVENUE AND THE COYOTE CREEK CROSSING, 40 FT. NORTHERLY OF THE CENTERLINE OF LINCOLN AVENUE AND 8 FT. EASTERLY OF THE NORTHWEST CORNER OF THE BRIDGE. MONUMENT IS SET 1.0 FT. BELOW THE ROAD.

