

Designation: FV-75-75

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q11-06

Page/Grid: 858/F-1

City / Location: Fountain Valley

Line #/SSN: 606/0030

Established By: OCS 1975

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
31.141	28.730	2010
31.282	28.857	1992

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 42 32.29	117 56 43.63

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "FV-75-75", SET IN THE NORTHWEST CORNER OF A 6 FT. BY 6 FT. CONCRETE VAULT. MONUMENT IS LOCATED IN THE SOUTHEAST CORNER OF THE INTERSECTION OF WARD STREET AND SLATER AVENUE, 30.1 FT. SOUTHERLY OF THE CENTERLINE OF SLATER AVENUE AND 12 FT. EASTERLY OF THE EAST END OF THE EAST SOUTHEAST CURB RETURN. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

