

Designation: FVPK

Date Destroyed:

Date Revised: 8/6/2013

GPS #: FVPK

OCS Index Map: Q11-11

Page/Grid: 888/G-1

City / Location: Costa Mesa

Line #/SSN:

Established By: Southern Calif. Integrated GPS Network

Monument Type: OCRTN

NO PHOTO

NAVD88 (ft)	NGVD29 (ft)	Year Leveled
80.250	77.840	2005 adj
80.318	77.907	2000

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 39 44.362839	117 56 08.520633

Description:

THIS IS A CONTINUOUS GPS STATION (CGPS) AND IS PART OF THE CALIFORNIA SPATIAL REFERENCE NETWORK (CSRN). DATA IS RECORDED AT 30 SECOND EPOCHS, 24 HOURS A DAY, 7 DAYS A WEEK AND CAN BE DOWNLOADED FROM THE SCRIPPS WEB SITE @ [HTTP://SOPAC.UCSD.EDU](http://SOPAC.UCSD.EDU). HORIZONTAL AND VERTICAL DATUM IS TO THE GEODETIC REFERENCE POINT (GRP). THE ANTENNA IS A TOPCON TPSCR.G3 (INSTALLED 06/08/2011). TRUE VERTICAL ANTENNA HEIGHT IS FROM THE GEODETIC REFERENCE POINT (GRP) TO THE BOTTOM OF THE ANTENNA PRE-AMP (BPA) AND IS 0.008 METERS (0.027 FEET).

