

## Designation: R-781

Date Destroyed:

Date Revised: 4/30/2007

GPS #:

OCS Index Map: Q07-13

Page/Grid: 799/G-6

City / Location: Santa Ana

Line #/SSN: 403/0430

Established By: USC & GS 1946

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
175.908	173.472	1988

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 46 29.889	117 51 22.925

### Description:

Due to RR construction (ballast was raised and wood retaining wall was installed) it is not possible to plumb a rod over point. DESCRIBED BY OCS 2002 - FOUND 3 3/4" NGS BRONZE DISK STAMPED "R 781 1946", SET IN THE SOUTHEASTERLY CORNER OF A CONCRETE BRIDGE. MONUMENT IS LOCATED IN THE SOUTHEASTERLY CORNER OF THE INTERSECTION OF THE ATCHINSON TOPEKA AND SANTA FE RAILROAD AND THE SANTIAGO CREEK OVERCROSSING, 0.1 MILES NORTHERLY ALONG THE RAILWAY FROM THE CENTERLINE OF FAIRHAVEN AVENUE, 2 FT. EASTERLY OF THE EASTERLY RAIL AND 8.5 FT. WESTERLY OF THE EASTERLY END OF THE SOUTHEAST BRIDGE ABUTMENT. MONUMENT IS SET 2.0 FT. BELOW THE TRACKS.

