

Designation: TIDAL-2

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q11-20

Page/Grid: 919/E-2

City / Location: Newport Beach

Line #/SSN: 406/0020

Established By: USC & GS 1926

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Levelled
9.970	7.635	2011
9.970	7.635	1994

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 35 49.44446	117 52 45.29130

Description:

RECOVERY NOTE BY OCS 2001 - FOUND 3 3/4" BRASS U.S. COAST AND GEODETIC SURVEY DISK STAMPED "No 2 1926" FLUSH IN SANDSTONE ROCK OUTCROPPING. MONUMENT IS LOCATED SOUTHWEST OF THE T-JUNCTION OF OCEAN BOULEVARD AND DAHLIA AVENUE, AT THE NEWPORT BAY ENTRANCE CHANNEL, IN TOP OF A ROCK LEDGE WHICH EXTENDS SOUTH FROM THE WILLIAM O. KERKOFF LABORATORY, 12 METERS (39.4 FT.) SOUTH OF THE SOUTH CORNER OF THE LAB, 8.1 METERS (26.6 FT.) SOUTHEAST OF TIDAL BENCHMARK 1, 7.3 METERS (24 FT.) NORTH OF THE SOUTH END OF THE ROCK LEDGE, 3.2 METERS (10.5 FT.) SOUTH OF THE SOUTH EDGE OF A STONE AND CEMENT WALL AROUND THE SOUTHWEST END OF THE LAB, THE STATION IS 1.8 METERS BELOW THE HEIGHT OF THE TOP OF THE WALL.

