

Designation: TIDAL-3NP

Date Destroyed:

Date Revised: 6/27/2011

GPS #:

OCS Index Map: Q11-20

Page/Grid: 919/D-2

City / Location: Newport Beach

Line #/SSN: 406/0110

Established By: NGS 1955

Monument Type: Bronze / Brass Disk



TIDAL-3NP

NAVD88 (ft)	NGVD29 (ft)	Year Leveled
10.673	8.325	2011
10.643	8.309	1994

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 36 12.48259	117 53 02.91628

Description:

RECOVERY NOTE BY OCS 2001 - FOUND 3 3/4" BRASS U.S. COAST & GEODETIC SURVEY DISK STAMPED "3 NP 1955" FLUSH IN CONCRETE. MONUMENT IS LOCATED AT THE ORANGE COUNTY HARBOR DISTRICT OFFICE, IN THE TOP OF THE SEAWALL, 68.9 METERS (226 FT.) NORTHWEST OF THE MARK STAMPED 2 NP 1955, 21.3 METERS (69.9 FT.) NORTHWEST OF THE WEST CORNER OF THE SHERIFF HARBOR PATROL OFFICE BUILDING, 13.7 METERS (44.9 FT.) SOUTHWEST OF THE SOUTHWEST WALL OF A SHOP BUILDING, 1.1 METERS (3.6 FT.) SOUTHEAST OF A CHAIN LINK FENCE. THE STATION IS LEVEL WITH THE HEIGHT OF THE GROUND.

