

Designation: W-130

Date Destroyed:

Date Revised:

GPS #: 1224

OCS Index Map: Q20-08

Page/Grid: 992/E-2

City / Location: San Clemente

Line #/SSN: 400/0110

Established By: USC & GS 1930

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
18.568	16.289	2005
18.568	16.289	1989

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 26 47.88422	117 39 08.37349

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" USCGS BRONZED BENCHMARK DISK STAMPED "W 130 1932", SET IN THE TOP OF A CONCRETE HEADWALL. MONUMENT IS LOCATED ALONG THE SOUTHWESTERLY SIDE OF EL CAMINO REAL, 0.5 MILES NORTHERLY ALONG EL CAMINO FROM THE CENTERLINE OF CAMINO CAPISTRANO, 21 FT. SOUTHWESTERLY OF THE CENTERLINE OF THE SOUTH BOUND LANES OF EL CAMINO AND 17.4 FT. NORTHEASTERLY OF THE NORTHEASTERLY RAIL ALONG THE ATCHINSON/TOPEKA/SANTA FE RAILWAY. MONUMENT IS SET 1 FT. BELOW THE LEVEL OF THE RAILWAY.

