

### Designation: X-130-R72

Date Destroyed: 6/1/2005

Date Revised:

GPS #:

OCS Index Map: Q20-12

Page/Grid: 992/G-4

City / Location: San Clemente

Line #/SSN: 400/0070

Established By: USC & GS 1972

Monument Type: Bronze / Brass Disk

NAVD88 (ft)	NGVD29 (ft)	Year Leveled
20.232	17.935	1989

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 25 54.02	117 37 57.38

#### Description:

DESCRIBED BY OCS 2004 - FOUND 3 3/4" NGS BRONZED BENCHMARK DISK STAMPED "X 130 RESET 1973", SET IN THE SOUTHERLY END OF A 2.5 FT. BY 26 FT. CONCRETE HEADWALL FOR A BOX CULVERT. MONUMENT IS LOCATED IN THE SOUTHWESTERLY PORTION OF THE INTERSECTION OF AVENUE ESTACION AND CALLE DESCHECA, 5.5 FT. WESTERLY OF THE WESTERLY RAIL ALONG THE ATCHINSON/TOPEKA/SANTA FE RAILWAY LINE, 11 FT. SOUTHERLY OF THE CENTERLINE OF THE CONCRETE BOX CULVERT. MONUMENT IS SET LEVEL WITH THE TOP OF THE WALL.