

Designation: X-130-R94

Date Destroyed:

Date Revised: 6/14/2005

GPS #:

OCS Index Map: Q20-12

Page/Grid: 992/G-4

City / Location: San Clemente

Line #/SSN: 400/1320

Established By: NGS 1994

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
20.276	17.979	2005

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 25 54.05	117 37 57.40

Description:

DESCRIBED BY OCS 2005 - FOUND 3 3/4" NGS BRONZED BENCHMARK DISK STAMPED "X 130 RESET 1994", SET AT THE SOUTHERLY END OF A 3.0 FT. BY 34 FT. CONCRETE HEADWALL FOR A BOX CULVERT. MONUMENT IS LOCATED IN THE SOUTHWESTERLY PORTION OF THE INTERSECTION OF AVENUE ESTACION AND CALLE DESCHECA ADJACENT TO THE SAN CLEMENTE METRO-LINK SUBSTATION, 5.2 FT. WESTERLY OF THE WESTERLY RAIL ALONG THE ATCHINSON/TOPEKA/SANTA FE RAILWAY LINE, 17 FT. SOUTHERLY OF THE CENTERLINE OF THE CONCRETE BOX CULVERT. MONUMENT IS SET LEVEL WITH THE TOP OF THE HEADWALL.

