

Designation: Y-785-R67

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q16-04

Page/Grid: 891/A-6

City / Location: Irvine

Line #/SSN: 356/0180

Established By: USC & GS 1967

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
385.033	382.667	1991

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 37 06.2	117 45 22.5

Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" USC&GS BRONZED DISK STAMPED "Y 785 1946 RESET 1967", SET IN THE TOP OF A 1 FT. DIAMETER CONCRETE POST. MONUMENT IS LOCATED ALONG THE EASTERLY SIDE OF LAGUNA CANYON ROAD STATE HIGHWAY 133, 1.74 MILES SOUTHERLY OF THE INTERSECTION OF HIGHWAY 133 AND THE LAGUNA ROAD, 42 FT. EASTERLY OF THE CENTERLINE OF STATE HIGHWAY 133, 252 FT. NORTHERLY OF THE END OF A CURVE, 1.2 FT. EASTERLY OF A USC&GS WITNESS POST, 0.7 FT. WESTERLY OF A 4 FT. HIGH BARBED WIRE FENCE AND 8.6 FT. EASTERLY OF A 18 IN. DIAMETER TREE. MONUMENT IS SET 3 FT. HIGHER THAN HIGHWAY 133.

