

## Designation: Z-785

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q16-04

Page/Grid: 921/A-1

City / Location: Laguna Beach

Line #/SSN: 356/0150

Established By: USC & GS 1946

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
339.630	337.269	1991

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 36 09.8	117 45 38.8

### Description:

DESCRIBED BY OCS 2004 - FOUND 3 3/4" USC&GS BRONZED DISK STAMPED "Z 785 1946", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED ALONG THE SOUTHEASTERLY SIDE OF LAGUNA CANYON ROAD, 5.2 MILES NORTHEASTERLY ALONG LAGUNA CANYON FROM THE CENTERLINE OF PACIFIC COAST HIGHWAY, 40 FT. EASTERLY OF THE CENTERLINE OF LAGUNA CANYON, 1.4 FT. WESTERLY OF A 4 FT. BARBED WIRE FENCE AND 7 FT. SOUTHEASTERLY OF POWER POLE #1322093E. MONUMENT IS SET 1.8 FT. BELOW THE ROAD LEVEL.

