

GPS #: 7641

Date Destroyed:
Date Revised: 10/15/2020
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 922/D-6
City / Location: Mission Viejo

Scale Factor: 0.99996219
Ellipsoid Red. Factor: 0.99998487
Combination Factor: 0.99994706
Convergence Angle: -00 46 18.56698

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 51.19948	117 39 16.37511	2151806.825	6133816.807	316.302
2007.00	33 33 51.21638	117 39 16.39105	2151808.55	6133815.48	
2017.50	33 33 51.22556	117 39 16.40121	2151809.49	6133814.63	316.302

References: MM 358/1-6, RSB 150/36-50, CR 2020-3248

Description:

FD TACK AND TAG IN CONC., (ILLEGIBLE), DOWN 1.6' IN WELL MONUMENT. ACCEPTED AS TACK AND TAG STAMPED "LS 3109" PER MM 358/1-6. STATION IS LOCATED AT THE CENTERLINE POINT OF REVERSE CURVE ALONG JARDINES ST., 0.1+/- MILE NORTH OF CROWN VALLEY PKWY.

