

**GPS #:** **2622**

Date Destroyed:

Date Revised: 9/22/2020

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/G-6

City / Location: Unin., Orange County

Scale Factor: 0.99996258

Ellipsoid Red. Factor: 0.99997462

Combination Factor: 0.99993720

Convergence Angle: -00 45 31.55110

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 11.02996	117 37 50.81662	2153714.362	6141082.534	530.694
2007.00	33 34 11.04678	117 37 50.83241	2153716.08	6141081.22	
2017.50	33 34 11.05597	117 37 50.84256	2153717.02	6141080.37	530.694

References: OCS SURVEY FILE # 989GL9179

## Description:

FD 2" BRASS OCS DISK STAMPED DOWN 1.7' IN OCS WELL MONUMENT. STATION IS LOCATED ALONG THE CENTERLINE OF ANTONIO PARKWAY, 0.3 MILES NORTHERLY FROM ITS INTERSECTION WITH CROWN VALLEY PARKWAY, SET IN THE GRASS MEDIAN.

