


Block 5852, Module 72
CORNER RECORD

Document Number WM 20W
CR98-319

City of UNINCORPORATED ORANGE COUNTY County of ORANGE, California
Brief Legal Description 100' ± SOUTH OF INTERSECTION OF FAIRHAVEN & FLINT DR.



CORNER TYPE

Government Corner ☐ Control ☒
Meander ☐ Property ☐
Rancho ☐ Other ☐
Date of Survey 6/22/98

COORDINATES

(Optional)
N 2228474.449
E 6084286.276
Zone 11 Datum 83
~~STW~~ 1991.35 EPOCH
(OCS ADJUST)

Corner — Left as found ☐ Found and tagged ☐ Established ☐ Reestablished ☒ Rebuilt ☐

Identification and type of corner found Evidence used to identify or procedure used to establish or reestablish the corner
REESTABLISHED MONUMENT BY HOLDING O.C.S.T.B A/S-9, 1985
BY FLYNN 12-18-85. ONE OF THE TIES WAS FOUND TO BE
DESTROYED, HAD THREE REMAINING TIES

A description of the physical condition of the monument as found and as set or reset SET LARGE
PUNCHED SPIKE AND 1/2" OCS BRASS WASHER IN A/C.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with
the Land Surveyors' Act on 13 JULY 1998

Signed TR Sandefur LS or RCE Number 5967



COUNTY SURVEYOR'S STATEMENT

This Corner Record was received JULY 30 1998 and examined
and filed JULY 30 1998

Signed Michael K Sullivan Title DEPUTY



County Surveyor's Comment _____

FAIRHAVEN

AVE.

(R) = RECORD PER
O.C.S.T.B. A/5-9
985

DR

100'±

FD CHIS "+" IN T.C.
PER O.C.S.T.B.
A/5-9 985

m d (R)
18.27'

m d (R)
47.06'

m d (R)
18.25'

FD CHIS. "+" IN
T.C. PER O.C.S.T.B.
A/5-9 985.

FD CHIS. "+" IN T.C.
PER O.C.S.T.B.
A/5-9 985

FLINT

47.77'

SET LG. PUN. SPK W/ 1 1/2"
OCS WASHER FLUSH
IN A/C

SET LD & BR NAIL
W/ 3/4" OCS TIE
TAG FLUSH IN T.C.



NO SCALE