


CORNER RECORD

Document Number 2009-3281City of ORANGE County of ORANGE, CaliforniaBrief Legal Description RE-ESTABLISHMENT OF CENTERLINE MONUMENT OF THE CITY DRIVE.
264m +/- S'LY OF METROPOLITAN DRIVE PER RECORD OF SURVEY 2003-1006.

CORNER TYPE

Government Corner	<input type="checkbox"/>	Control	<input type="checkbox"/>
Meander	<input type="checkbox"/>	Property	<input type="checkbox"/>
Rancho	<input type="checkbox"/>	Other	<input checked="" type="checkbox"/>

Date of Survey AUGUST 12, 2009

COORDINATES (Optional)

N. _____
E. _____
Zone _____ NAD27 ☐ NAD83 ☐
NAD83 Epoch _____
Elev. _____
Vert. Datum: NGVD29 ☐ NAVD83 ☐
Meas. Units: Metric ☒ Imperial ☐
U.S. Survey foot ☐

Corner — Left as found ☐ Found and tagged ☐ Established ☐ Reestablished ☒ Rebuilt ☐

Identification and type of corner found; Evidence used to identify or procedure used to establish or reestablish the corner:
IT IS THE PURPOSE OF THIS CORNER RECORD TO PERPETUATE THE POSITION OF THE 2 1/4" BRASS
DISK STAMPED "CALIFORNIA DIVISION OF HIGHWAYS" IN WELL MONUMENT DOWN 0.30m (1.0')
PT. 132 PER RECORD OF SURVEY 2003-1006, R.S.B. 199/1-16. THE POSITION WAS RE-ESTABLISHED BY
UTILIZING IT'S GRID STATE PLANE COORDINATE VALUE AS SHOWN ON RECORD OF SURVEY
2003-1006. STATIC GPS VALUES WERE ESTABLISHED ON 2 TEMPORARY CONTROL POINTS AND
THE POSITION WAS "DOUBLE DETERMINED".
A description of the physical condition of the monument as found and as set or reset: _____
UNSAFE TO SET ACTUAL MONUMENT POSITION AS IT FALLS IN A TRAFFIC LANE WITH POOR
VISIBILITY UNDER THE FREEWAY BRIDGE. SET LEAD, TACK AND TAG "TIE POINT PLS 6343"
ON CENTERLINE TANGENTS PRODUCED.

SURVEYOR'S STATEMENT

This Corner Record was prepared by me or under my direction in conformance with
the Land Surveyor's Act on AUGUST 28, 2009Signed James L. Garvin L.S. NO. 6343

COUNTY SURVEYOR'S STATEMENT

This Corner Record was received NOV 10 2009
and examined and filed DEC 17 2009Signed J. C. Hornecker L.S. or R.C.E. No. 7212
Title DEPUTY COUNTY SURVEYOR

County Surveyor's Comment _____

LEGEND

□ SET LEAD, TACK AND TAG "TIE POINT PLS 6343" IN TOP OF CURB, UNLESS NOTED OTHERWISE.

(xxx) INDICATES RECORD DATA PER RECORD OF SURVEY 2003-1006, R.S.B. 199/1-16.

ALL DISTANCES SHOWN ARE GRID, UNLESS OTHERWISE NOTED. TO OBTAIN GROUND DISTANCES MULTIPLY GRID DISTANCE BY 1.00001709.

