

GPS #: 0015

Date Destroyed: 7/25/2000

Date Revised: 1/22/2003

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/B-4

City / Location: La Palma

Scale Factor: 0.99999352

Ellipsoid Red. Factor: 1.00000372

Combination Factor: 0.99999724

Convergence Angle: -00 59 30.00173

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 34.94970	118 03 16.61063	2255127.127	6013716.732	-77.716
2007.00	33 50 34.96578	118 03 16.62878	2255128.78	6013715.23	

References: NGS PID# DY2405, RSB 149/21-36

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 3/4" BRASS N.G.S. DISK STAMPED "DENNI 1974" SET IN THE TOP OF A 12" DIA. CONC. POST 0.15' BELOW THE GROUND SURFACE. TO REACH THE STATION FROM THE INTER OF MOODY ST. AND CRESENT AVE., IN THE CITY OF LA PALMA, PROCEED W'LY ALONG CRESENT AVE. 0.5 MILE TO DENNI ST. TURN RIGHT ALONG DENNI ST. AND PROCEED N'LY 0.25 MILE TO END OF RD. AND STATION SITE. STATION IS LOCATED E'LY FROM THE PROD OF THE CENTERLINE OF DENNI ST. N'LY FROM THE EXISTING END OF THE PAVED RD.