

GPS #: 0022

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 799/B-4

City / Location: Garden Grove

Scale Factor: 0.99998529

Ellipsoid Red. Factor: 0.99999146

Combination Factor: 0.99997675

Convergence Angle: -00 54 22.69045

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 12.40322	117 53 57.37232	2233874.197	6060557.144	178.379
2007.00	33 47 12.41945	117 53 57.38928	2233875.86	6060555.74	

References: NGS PID# DX4790, RSB 149/10-20

Description:

FD 1" SQUARE METAL PLUG WITH A CENTER PUNCH CEMENTED IN A CONC. SLAB 16.5' WEST OF THE EAST EDGE OF SAID SLAB. IT IS THE NW 1/4, SECTION 35, TOWNSHIP 4 SOUTH, RANGE 10 WEST. THE STATION IS LOCATED ON THE ROOF OF THE GARDEN GROVE COMMUNITY CHURCH "TOWER OF HOPE".

