

GPS #: 0028

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/E-7

City / Location: Aliso Viejo

Scale Factor: 0.99996206

Ellipsoid Red. Factor: 0.99999371

Combination Factor: 0.99995578

Convergence Angle: -00 48 31.00158

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 44.97177	117 43 17.37665	2151458.658	6113416.676	133.304
2007.00	33 33 44.98891	117 43 17.39274	2151460.41	6113415.34	

References: MM 629/37-39

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS TAG
STAMPED "LS 4541", SET FLUSH IN ASPHALT.
LOCATED SE OF THE INTER OF ALISO CREEK RD.
AND LAGUNA HILLS RD.; AT THE INTER OF
DEERHURST AND LAGUNA HILLS RD.

