

**GPS #:** 0032

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/F-3

City / Location: Laguna Niguel

Scale Factor: 0.99996054

Ellipsoid Red. Factor: 0.99999297

Combination Factor: 0.99995351

Convergence Angle: -00 48 18.39282

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 32 21.49749 | 117 42 54.43151 | 2142994.818   | 6115239.549  | 148.924               |
| 2007.00          | 33 32 21.51453 | 117 42 54.44763 | 2142996.56    | 6115238.21   |                       |

References: OCS SURVEY FILE # R91-72

## Description:

FD BRASS NAIL AND 1 1/4" BRASS OCS TAG STAMPED "MARS BONFIRE 93" IN LEAD, FLUSH IN CONC. OF SIDEWALK. LOCATED SOUTH FROM THE INTER OF ALICIA PKWY. AND ALISO CREEK RD., AT THE INTER OF ALICIA PKWY. AND HIGHLANDS AVE; ON THE SIDEWALK EAST OF ALICIA PKWY.

