

**GPS #:** 0033

**Date Destroyed:** 7/25/2000

**Date Revised:**

**Benchmark Designation:**

**OCS Index Map:** 5LB

**Page/Grid:** 861/G-7

**City / Location:** Irvine

**Scale Factor:** 0.99997071

**Ellipsoid Red. Factor:** 0.99998353

**Combination Factor:** 0.99995425

**Convergence Angle:** -00 47 57.34867

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 51.79976	117 42 16.13582	2188460.772	6119115.594	346.144
2007.00	33 39 51.81627	117 42 16.15189	2188462.46	6119114.26	

**References:** OCS SURVEY FILE # T93/94-2S

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 5/8" REBAR WITH OCS PLASTIC CAP AND 1 1/4" OCS BRASS TAG STAMPED "TRAV 3 - GPS 0033", DOWN 0.3'. LOCATED IN A NW'LY DIRECTION FROM THE INTER OF IRVINE BLVD. AND ALTON PKWY.; SET BY THE CORNER OF A BARBED WIRE FENCE BETWEEN EL TORO MARINE CORPS AIR STATION PROPERTY AND THE SW CORNER OF JAMES MUSICK BRANCH JAIL PROPERTY.