

GPS #: 0039

Date Destroyed: 5/9/1996

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/F-6

City / Location: Orange

Scale Factor: 0.99999058

Ellipsoid Red. Factor: 0.99997251

Combination Factor: 0.99996309

Convergence Angle: -00 50 37.23974

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 25.25995	117 47 07.10208	2246773.613	6095378.777	574.431
2007.00	33 49 25.27592	117 47 07.11904	2246775.25	6095377.37	

References: RSB 143/30-35, RSB 149/10-20

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 3/4" PUNCHED O.C.S. ALUMINUM DISK STAMPED "LEMON" SET IN 8" DIA. CONC. MONUMENT, DOWN 0.2', LOCATED ON TOP OF HILL NE'LY FROM THE INTER OF SERRANO AVE. AND YELLOWSTONE BLVD.