

GPS #: 0051

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 740/F-7

City / Location: Yorba Linda

Scale Factor: 0.99999745

Ellipsoid Red. Factor: 0.99998037

Combination Factor: 0.99997782

Convergence Angle: -00 50 39.39948

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 04.15844	117 47 11.03232	2262839.034	6095283.905	410.193
2007.00	33 52 04.17483	117 47 11.04882	2262840.71	6095282.54	

References: RSB 143/30-35, RSB 149/1-9

Description:

FD 2 1/2" O.C.S. BRASS DISK WITH CROSS CUT MARK STAMPED "YORBA G.P.S. 2-88-AO" IN 6" DIA. CONC. COLLAR FLUSH IN GROUND, LOCATED ON TOP OF RIDGE SOUTH FROM 2 LARGE WATER TANKS, SOUTH OF LARKRIDGE DR.

