

GPS #: 0056

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 772/C-2

City / Location: Unin., Orange County

Scale Factor: 0.99999447

Ellipsoid Red. Factor: 0.99986065

Combination Factor: 0.99985512

Convergence Angle: -00 46 15.70188

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 57.04329	117 39 11.16124	2255484.895	6135653.313	2912.527
2007.00	33 50 57.05978	117 39 11.17779	2255486.58	6135651.94	

References: RSB 143/30-35

Description:

FD 3 3/4" O.C.S. ALUMINUM BENCHMARK DISK WITH CROSS CUT MARK STAMPED "3R-75-71" IN 6" X 6" CONC. POST UP 0.6', LOCATED ON SIER PEAK.

