

GPS #: 0058

Date Destroyed: 3/13/1997

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/H-1

City / Location: Unin., Orange County

Scale Factor: 0.99996496

Ellipsoid Red. Factor: 0.99995655

Combination Factor: 0.99992152

Convergence Angle: -00 45 00.04285

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 03.46605	117 36 53.47862	2165014.308	6146082.426	907.938
2007.00	33 36 03.48292	117 36 53.49442	2165016.03	6146081.11	

References: RSB 143/30-35, RSB 151/1-11

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 1/2" U.S.C. & G.S. BRASS DISK STAMPED "CHIQUITA NO. 1 1939" WITH AN ARROW POINTING W'LY, SET IN CONC. UP 0.5', LOCATED ON RIDGE NW'LY FROM CHIQUITA CANYON.