

GPS #: 0061

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 833/H-7

City / Location: Unin., Orange County

Scale Factor: 0.99997548

Ellipsoid Red. Factor: 0.99973648

Combination Factor: 0.99971196

Convergence Angle: -00 42 22.24957

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 31.65632	117 32 06.32986	2203940.806	6170851.932	5508.319
2007.00	33 42 31.67331	117 32 06.34553	2203942.54	6170850.63	

References: RSB 143/30-35

Description:

FD PUNCHED SHANK OF AN O.C.S. DISK SET IN A 1" I.P., SET IN 15" X 18" CONC. MONUMENT FLUSH WITH ROCK SURFACE. ORIGINAL MONUMENT DISK HAS BEEN BROKEN OFF, LOCATED ON TOP OF SANTIAGO PEAK.

