

GPS #: 0067

Date Destroyed:

Date Revised: 5/10/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 973/F-1

City / Location: Unin., Orange County

Scale Factor: 0.99996124

Ellipsoid Red. Factor: 0.99997189

Combination Factor: 0.99993313

Convergence Angle: -00 43 02.78185

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 00.77370	117 33 20.08962	2146318.524	6163898.777	587.463
2007.00	33 33 00.79071	117 33 20.10532	2146320.26	6163897.47	

References: OCS FILE # OC96/7-7, GEODETIC UNIT

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "ORTEGA" SET IN 6" DIA. CONC. COLLAR, UP 0.2' IN DIRT WITH 4' HIGH, 2" IRON GATE POST LOCATED 3' SE'LY. MONUMENT IS LOCATED FROM THE INTER OF THE 405 FREEWAY AND ORTEGA HWY., PROCEED E'LY ALONG ORTEGA HWY. 7.6 MILES TO THE CASPERS REGIONAL PARK ENTRANCE ON LEFT. PROCEED INTO THE PARK, PAST ENTRANCE GATE AND ALONG MAIN A.C. ROAD, TO A STOP SIGN AT A "T" INTER. TURN RIGHT AND CONTINUE 0.2 MILES TO A LOCKED WOOD GATE (DA1) ON RIGHT, JUST BEFORE RESTROOMS ON LEFT. TURN RIGHT AND PROCEED THRU SAID GATE AND CONTINUE UPHILL ALONG ROUGH DIRT RD. N'LY AND ALONG THE RIDGE 0.8 MILES TO SAID MONUMENT LOCATED ON TOP OF HILL AND 20' LEFT OF DIRT ROAD.

