

GPS #: 0070

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 953/G-6

City / Location: San Juan Capistrano

Scale Factor: 0.99995897

Ellipsoid Red. Factor: 0.99995482

Combination Factor: 0.99991380

Convergence Angle: -00 42 49.55602

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 30 44.83520 | 117 32 56.02152 | 2132553.952 | 6165764.385 | 945.933 |
| 2007.00 | 33 30 44.85203 | 117 32 56.03720 | 2132555.67 | 6165763.08 | |

References: OCS SURVEY FILE # GPS93/94-2N

Description:

FD 3 3/4" DIA. ALUMINUM OCS TRIANGULATION DISK STAMPED "7-6-31", SET IN 8" DIA. CONC./PVC CASING, UP 0.2'. LOCATED IN AN E'LY DIRECTION FROM THE INTER OF ORTEGA HWY. AND A DIRT RD. KNOWN AS CLAY PIT RD.; SET NEAR THE TOP OF A HILL APPROX. 75' EAST OF A BARBED WIRE FENCE.

