

GPS #: **0072**

Date Destroyed:

Date Revised: 4/1/1997

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/G-4

City / Location: Unin., Orange County

Scale Factor: 0.99996359

Ellipsoid Red. Factor: 0.99996004

Combination Factor: 0.99992363

Convergence Angle: -00 44 38.84096

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 00.18388	117 36 14.89588	2158575.862	6149262.515	835.048
2007.00	33 35 00.20080	117 36 14.91168	2158577.59	6149261.20	

References: OCS FILE # OC96/7-7, GEODETIC UNIT

Description:

FD 3 3/4" ALUMINUM OCS TRIANGULATION DISK STAMPED "7-7-10" SET IN 9" DIA. CONC. MONUMENT, UP 0.8' FROM DIRT, LOCATED FROM THE INTER OF ANTONIO PKWY. AND OSO PKWY., PROCEED E'LY 2.0 MILES ALONG OSO PKWY. TO A DIRT RD. ON RIGHT. PROCEED S'LY ALONG SAID DIRT RD. 0.5 MILES TO A BARBED WIRE GATE (DA1 LOCK). PROCEED THRU GATE, S'LY 0.3 MILES TO AN APPARENT "T" INTER AND PARK. HIKE E'LY UPHILL ALONG THE RIDGE 400' +/- TO FENCE POST AND CONTINUE E'LY 200' +/- TO SAID MONUMENT

