

GPS #: 0074

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 923/D-1

City / Location: Coto De Caza

Scale Factor: 0.99996509

Ellipsoid Red. Factor: 0.99995884

Combination Factor: 0.99992393

Convergence Angle: -00 43 42.26820

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 09.12467	117 34 31.94600	2165431.780	6158059.933	857.862
2007.00	33 36 09.14151	117 34 31.96179	2165433.50	6158058.62	

References: OCS SURVEY FILE # GPS93/94-2N

Description:

FD 3 3/4" DIA. ALUMINUM TRIANGULATION DISK, STAMPED "6-7-35", SET IN 8" CONC./PVC MONUMENT, UP 0.65'. LOCATED EAST OF THE INTER OF COTO DE CAZA DR. AND SAN MIGUEL; SET OFF A DIRT RD., ON THE TOP OF A HILL SE OF THE INTER OF SAN MIGUEL RD. AND DEL VERDE RD.

