

GPS #: **0075**

Date Destroyed:

Date Revised: 4/1/1997

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 893/A-7

City / Location: Unin., Orange County

Scale Factor: 0.99996592

Ellipsoid Red. Factor: 0.99994703

Combination Factor: 0.99991295

Convergence Angle: -00 44 29.30083

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 45.08210	117 35 57.53496	2169158.850	6150868.334	1106.983
2007.00	33 36 45.09904	117 35 57.55064	2169160.58	6150867.03	

References: OCS FILE # OC96/7-7, GEODETIC UNIT

Description:

FD 3 3/4" ALUMINUM OCS DISK STAMPED "6-7-34" SET IN 9" DIA. CONC. MONUMENT, UP 0.4' FROM DIRT, LOCATED FROM THE INTER OF ANTONIO PKWY. AND BIENVENIDOS, PROCEED SE'LY THRU RIGHT-HAND (SW'LY) OF 2 CHAIN LINKED GATES ENTERING TIJERAS CREEK HIKING TRAIL. (DA1 LOCK). FOLLOW DIRT RD. SW'LY ALONG CREEK 0.2 MILES TO A "T" INTER ON LEFT. PROCEED LEFT, UPHILL AND NE'LY, 0.3 MILES TO ANOTHER "T" INTER ON RIGHT. PROCEED RIGHT, SW'LY, ALONG RIDGE 1.0 MILE TO JUNCTION ON LEFT. PROCEED LEFT, E'LY, TO SECOND RIDGE HEADING SW'LY. CONTINUE 0.7 MILES TO HARD LEFT TURN WITH CLEARING ON RIGHT. PARK HERE AND PROCEED ON FOOT SW'LY AND UPHILL 150' +/- TO MINOR RIDGE HEADING W'LY. PROCEED W'LY ALONG SAID RIDGE 450' +/- TO SAID MONUMENT.

