

GPS #: 0089

Date Destroyed:

Date Revised: 4/13/2000

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/E-6

City / Location: Unin., Orange County

Scale Factor: 0.99997721

Ellipsoid Red. Factor: 0.99997791

Combination Factor: 0.99995512

Convergence Angle: -00 48 25.36847

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 25.23694	117 43 07.12565	2210093.407	6115110.166	461.528
2007.00	33 43 25.25340	117 43 07.14151	2210095.09	6115108.85	

References: MONITORING SURVEYS 1997

Description:

East Hicks Canyon Dam Monitoring Station 4+50 - FD
3" OCS DISK WITH "+" DN 0.5' IN ALUMINUM WELL
MONUMENT LOCATED ON TOP OF NORTHERLY
PORTION OF DAM.

