

GPS #: 0090

Date Destroyed:

Date Revised: 4/13/2000

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/E-4

City / Location: Unin., Orange County

Scale Factor: 0.99997849

Ellipsoid Red. Factor: 0.99997224

Combination Factor: 0.99995074

Convergence Angle: -00 48 19.74405

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 03.83372	117 42 56.89047	2213982.281	6116029.430	580.091
2007.00	33 44 03.85024	117 42 56.90637	2213983.97	6116028.11	

References: MONITORING SURVEYS 1997

Description:

Hicks Canyon Dam Monitoring Station 6+00 - FD 3"
OCS DISK WITH "+" DN 0.5' IN ALUMINUM WELL
MONUMENT LOCATED ON TOP OF SOUTHERLY
PORTION OF DAM.

