

**GPS #:** 0091

Date Destroyed:

Date Revised: 4/13/2000

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/E-4

City / Location: Unin., Orange County

Scale Factor: 0.99997871

Ellipsoid Red. Factor: 0.99997223

Combination Factor: 0.99995094

Convergence Angle: -00 48 20.78512

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 10.12852	117 42 58.78497	2214620.757	6115878.396	580.284
2007.00	33 44 10.14498	117 42 58.80095	2214622.44	6115877.07	

References: MONITORING SURVEYS 1997

**Description:**

Hicks Canyon Dam Monitoring Station 8+00 - FD 3"  
OCS DISK WITH "+" DN 0.5' IN ALUMINUM WELL  
MONUMENT LOCATED ON TOP OF NORTHERLY  
PORTION OF DAM.

