

GPS #: 0093R1

Date Destroyed:

Date Revised: 4/27/2001

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/F-5

City / Location: Lake Forest

Scale Factor: 0.99997168

Ellipsoid Red. Factor: 0.99995639

Combination Factor: 0.99992808

Convergence Angle: -00 45 43.39630

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 25.77781	117 38 12.37225	2191614.256	6139762.594	
2007.00	33 40 25.79449	117 38 12.38783	2191615.96	6139761.30	

References: OCS SURVEY FILE # R93/94-18S, CR 2001-0848

Description:

FD LEAD AND TACK WITH 1 1/2" BRASS OCS TAG STAMPED "0093R1 04/01" FLUSH IN SIDEWALK, IN LIEU OF 2" I.P. WITH 2 1/2" BRASS OCS DISK STAMPED "GPS 0093 11-93". MONUMENT WAS RESET PER CORNER RECORD # 2001-848. MONUMENT IS LOCATED AT THE INTER OF GLEN RANCH RD. AND SADDLEBACK RANCH RD.; SET IN A NW'LY DIRECTION 6' FROM THE NW CURB RETURN.

