

**GPS #:** 0103

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 709/C-6

City / Location: Brea

Scale Factor: 1.00000721

Ellipsoid Red. Factor: 0.99998610

Combination Factor: 0.99999331

Convergence Angle: -00 53 57.10362

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 29.65091	117 53 10.80996	2284070.619	6065275.461	290.551
2007.00	33 55 29.66762	117 53 10.82692	2284072.33	6065274.06	

References: NGS PID# DX4813, RSB 149/21-36

## Description:

FD 3 3/4" O.C.S. ALUMINUM DISK STAMPED "3-10-12 1974" SET IN TOP OF 12" DIA. CONC. BLOCK FLUSH IN SURFACE. TO REACH MONUMENT FROM THE INTER OF STATE COLLEGE BLVD. AND LAMBERT RD., IN THE CITY OF BREA, PROCEED WEST 0.2 MILE TO #630 EAST LAMBERT RD., TO THE W'LY ASPHALT DR. OF THE BRISTOL COMPANY. STATION IS LOCATED AT THE NE CORNER OF A OPEN FIELD 15' WEST OF THE WEST EDGE OF THE ASPHALT DR., 28' SOUTH OF THE SOUTH CURB OF LAMBERT RD.

