

GPS #: **0104**

Date Destroyed: **8/1/2012**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LB**

Page/Grid: **862/F-6**

City / Location: **Lake Forest**

Scale Factor: **0.99997135**

Ellipsoid Red. Factor: **0.99995390**

Combination Factor: **0.99992526**

Convergence Angle: **-00 45 34.94967**

*Factors and Convergence Angle based on
the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 14.40933	117 37 57.00123	2190447.980	6141046.280	965.142
2007.00	33 40 14.42607	117 37 57.01679	2190449.69	6141044.99	

References: **OCS SURVEY FILE # R93/94-18S**

Description:

**REPORTED DESTROYED (SEE DATE IN DESTROYED
BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P.
WITH 2 1/2" BRASS OCS DISK STAMPED "GPS 0104
11-93", FLUSH. LOCATED SE FROM THE INTER OF
GLEN RANCH RD. AND SADDLEBACK RANCH RD.;
SET IN THE DIRT, OFF GLEN RANCH RD., 10' NORTH
OF THE N'LY CURB.**