

GPS #: **0120**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LB**

Page/Grid: **862/G-6**

City / Location: **Lake Forest**

Scale Factor: **0.99997136**

Ellipsoid Red. Factor: **0.99995668**

Combination Factor: **0.99992805**

Convergence Angle: **-00 45 26.33828**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 14.87224	117 37 41.33045	2190477.234	6142371.205	906.944
2007.00	33 40 14.88894	117 37 41.34592	2190478.94	6142369.92	

References: **OCS SURVEY FILE # R93/94-18S**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P. WITH 2 1/2" BRASS OCS DISK STAMPED "GPS 0120 11-93", SET FLUSH. LOCATED NW OF THE INTER OF GLEN RANCH RD. AND EL TORO RD.; SET APPROX. 75' WEST OF THE W'LY END OF A BRIDGE CROSSING ALISO CREEK AND 75' NORTH OF THE N'LY CURB OFF GLEN RANCH RD. ACROSS A CONC. GUTTER.