

GPS #: 0123

Date Destroyed:

Date Revised: 6/5/1996

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 769/F-5

City / Location: Anaheim

Scale Factor: 0.99999245

Ellipsoid Red. Factor: 0.99999500

Combination Factor: 0.99998745

Convergence Angle: -00 53 16.11307

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 09.99374	117 51 56.21627	2251663.518	6071059.944	104.478
2007.00	33 50 10.01007	117 51 56.23358	2251665.19	6071058.51	

References: RSB 149/1-9

Description:

FD PUNCHED SPIKE WITH O.C.S. TAG STAMPED "RCE 6978 4-75" FLUSH ON A.C. SURFACE LOCATED W'LY FROM SANTA ANA RIVER, ON THE N'LY SIDE OF LINCOLN AVE., 4 ' W'LY FROM THE W'LY END OF A A.C. CURB AND 35 ' +/- S'LY FROM AN E'LY FENCE POST.

