

GPS #: **0125**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/B-3

City / Location: La Habra

Scale Factor: 1.00000339

Ellipsoid Red. Factor: 0.99997986

Combination Factor: 0.99998325

Convergence Angle: -00 56 54.59452

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 54 11.75504	117 58 33.80401	2276636.260	6037930.326	420.928
2007.00	33 54 11.77123	117 58 33.82162	2276637.92	6037928.87	

References: NGS PID# DX4826, RSB 149/21-36

Description:

FD 3 5/8" U.S.C. & G.S. BRASS DISK STAMPED "COYOTE" SET IN CONC. IN 9" DIA. METAL CASING DOWN 0.5' BELOW GROUND SURFACE LOCATED, IN THE STANDARD OIL COMPLEX.

