

**GPS #:** 0130

Date Destroyed:

Date Revised: 7/1/2000

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 739/B-3

City / Location: Fullerton

Scale Factor: 1.00000207

Ellipsoid Red. Factor: 0.99998078

Combination Factor: 0.99998286

Convergence Angle: -00 54 19.65039

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 44.12580	117 53 51.84012	2273459.154	6061649.760	401.623
2007.00	33 53 44.14237	117 53 51.85714	2273460.85	6061648.35	

References: NGS PID# DX4817, RSB 149/21-36

## Description:

FD U.S.C. & G.S. BRASS DISK STAMPED "UNION 118 NO. 3 1969" CEMENTED IN TOP OF 12" SQUARE CONC. MONUMENT UP 0.1' ABOVE GROUND SURFACE. OCS 87/1/00 - Located from the intersection of State College and Bastauchury Road proceed w'ly along Bastauchury Rd. approx. 50 yds. to the entrance of the "Summit House" restaurant on the left. Turn left onto this entrance road and proceed up the small hill 0.7 mi. to a chain link gate and driveway entrance for the golf course on the right. Proceed through the gate and to the right 350' down the small hill past "HOLE 75" oil well on the right to the graveled road that leads up the hill to the left. Proceed through the chain link gate (sign indicates PARK AND PARKING LOT CLOSED..." times) up the hill through the switchback and along the dirt road 0.24 mi. (1270'), across the golf cart path, past the view loop on the right, to a telephone pole where the telephone line continues down the hill steeply. GPS 0130 and it's orange carsonite survey marker is 20' e'ly of said telephone pole.

