

GPS #: 0132

Date Destroyed:

Date Revised: 6/21/1999

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/F-3

City / Location: Fullerton

Scale Factor: 1.00000270

Ellipsoid Red. Factor: 0.99999280

Combination Factor: 0.99999550

Convergence Angle: -00 55 46.90306

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 57.20655	117 56 30.62058	2274995.614	6048288.176	150.446
2007.00	33 53 57.22269	117 56 30.63793	2274997.27	6048286.74	

References: RSB 149/21-36, A/3-10, 27

Description:

FD PUNCHED DURAL BAR DOWN 1.0' IN O.C.S. WELL MONUMENT LOCATED AT THE CENTERLINE P.I. OF EUCLID STREET, 78.83' NORTHEASTERLY FROM THE B.C. OF EUCLID STREET, 0.5 +/- MILE NORTHEASTERLY FROM ITS INTERSECTION WITH ROSECRANS AVENUE.

