

GPS #: **0133**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **2L**

Page/Grid: **770/F-5**

City / Location: **Orange**

Scale Factor: **0.99999192**

Ellipsoid Red. Factor: **0.99995209**

Combination Factor: **0.99994401**

Convergence Angle: **-00 50 37.52208**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 57.43200	117 47 07.61589	2250025.999	6095383.324	1001.215
2007.00	33 49 57.44803	117 47 07.63269	2250027.64	6095381.93	

References: NGS PID# DX4721, RSB 149/10-20

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 1/2" BRASS O.C.S. TRIANGULATION DISK STAMPED "OLIVE NO. 1 1939" IN A 12" SQUARE CONC. PAD UP 0.1' FROM SURFACE LOCATED, IN THE HILLS BETWEEN ANAHEIM HILLS AND VILLA PARK.