

GPS #: 0146

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/H-3

City / Location: San Clemente

Scale Factor: 0.99995571

Ellipsoid Red. Factor: 0.99999963

Combination Factor: 0.99995535

Convergence Angle: -00 45 12.75980

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 26 08.96387	117 37 16.62063	2104955.096	6143334.903	9.252
2007.00	33 26 08.98085	117 37 16.63604	2104956.83	6143333.62	

References: PMB 111/27

Description:

FD 1 1/2" I.P. AND 1" RCE 10035 TAG WITH NAIL, DOWN 0.1', PER PARCEL MAP 111-27. LOCATED IN A SE'LY DIRECTION FROM THE INTER OF AVENIDA PICO AND CALLE DE LOS MOLINOS; SET 5' EAST OF THE E'LY CURB OF AVENIDA SIERRA AT THE FIRST EC.

