

GPS #: **0157**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 862/J-7

City / Location: Unin., Orange County

Scale Factor: 0.99997003

Ellipsoid Red. Factor: 0.99994165

Combination Factor: 0.99991168

Convergence Angle: -00 44 46.07645

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 26.65794	117 36 28.06286	2185522.916	6148499.432	1219.486
2007.00	33 39 26.67474	117 36 28.07829	2185524.63	6148498.15	

References: OCS SURVEY FILE # 088-1, RSB 151/1-11

Description:

FD 2 1/2" BRASS DISK STAMPED "T6S R7W S9/S10/S16/S15 RE4231 RE2839" IN 2" I.P. UP 0.4' ABOVE GROUND SURFACE LOCATED BY THE O'NEILL REGIONAL PARK AREA.

