

GPS #: **0176**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 828/A-3

City / Location: Midway City

Scale Factor: 0.99997999

Ellipsoid Red. Factor: 1.00000370

Combination Factor: 0.99998371

Convergence Angle: -00 57 12.85034

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 47.62367	117 59 07.02555	2219665.688	6034181.457	-76.329
2007.00	33 44 47.63997	117 59 07.04243	2219667.36	6034180.06	

References: OCS SURVEY FILE # 93/94-3N, CR 2001-1126

Description:

MONUMENT LOCATION FALLS ON TOP OF MANHOLE; SET (4), 2' C-NAIL TIES FLUSH IN ASPHALT, LOCATED AT THE INTER OF WASHINGTON AVE. AND MONROE ST.,

