

GPS #: **0188**

Date Destroyed: **1/1/1998**

Date Revised:

Benchmark Designation:

OCS Index Map: 4IA

Page/Grid: 828/B-2

City / Location: Midway City

Scale Factor: 0.99998069

Ellipsoid Red. Factor: 1.00000330

Combination Factor: 0.99998408

Convergence Angle: -00 57 04.36953

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 07.39005	117 58 51.59236	2221641.781	6035517.652	-69.485
2007.00	33 45 07.40633	117 58 51.60917	2221643.45	6035516.26	

References: OCS SURVEY FILE # 93/94-3N, SAME AS GPS# 4223

Description:

MONUMENT LOCATION FALLS ON TOP OF MANHOLE; SET (4), 3' C-NAIL TIES, PER GPS RECORD SHEET 4223. LOCATED AT THE INTER OF NEWLAND ST. AND HAZARD AVE.